
FLUTED PANELS


PREFINISHED INTERLOCKING












































































































INSTALLATION

- Panel the wall with either aluminum channels or plywood as the base
- Fixing the panel: Drill screws on the lower side of the 1st panel at intermitted distance
- Overlap the upper side of the 2nd panel on the 1st panel
- Again drill the screws on the lower side of the 2nd panel
- As we repeat the process, screws are hidden & we achieve perfectly consistent panelling



MANUFACTURING PROCESS

- Refining raw wood fibres for quality.
- Gluing, pressing & calibrating into uniform panels.
- Routing wooden panels into desired designs.
- Applying textured PVC finishes on top layer.



CORE: Engineered Wood (HMR-Grade MDF)

FINISH: Textured PVC Membrane

HEIGHT: 9ft (2750mm)

WIDTH 121mm (4.75 inches)

THICKNESS: 18mm (3/4th inch)



